



# Annex 18

## Performance Warranty Schedule

### Macao Solar Installation

#### REVISION HISTORY

Revision Level	Change Summary	Elaborated by	Approved by	Date

## 1. Provisional Acceptance Test (PAT)

<b>Year 0</b>	<i>Theoretical Performance Ratio</i>	<b><i>Guaranteed Performance Ratio</i></b>	<i>T<sub>mod</sub>[°C]</i>
Jan	81.97%	79.92%	44.92
Feb	84.05%	81.95%	42.38
Mar	86.62%	84.45%	38.39
Apr	89.18%	86.95%	30.39
May	91.42%	89.13%	23.94
Jun	92.39%	90.08%	20.45
Jul	92.90%	90.58%	21.28
Aug	91.76%	89.47%	22.38
Sep	90.01%	87.76%	27.36
Oct	87.74%	85.55%	32.00
Nov	83.57%	81.48%	39.59
Dec	82.67%	80.60%	41.63
Year 0	86.26%	84.10%	33.08

For the avoidance of doubts, the Guaranteed PR is equal to 97.5% of the Theoretical PR.  
Minimum PR at PAC is equal to 92% of the theoretical PR.

## 1. Intermediate and Final Acceptance Test (IAT and FAT)

Year	Test	<i>Theoretical Performance Ratio</i>	<b><i>Guaranteed Performance Ratio</i></b>	Annual Degradation	Minimum PR
1	IAT	86.09%	86.09%	0.4%	79.20%
2	FAT	85.75%	85.75%		78.89%